## GENERAL NOTES

1. OWNER/DEVELOPER: PRINCE GEORGE COUNTY
   P.O. BOX 68
   PRINCE GEORGE, VA 23875
   TEL. (804)733-2600
   FAX. (804)733-2602
   ATTN.: WILLIAM E. JOHNSON

2. CONSULTING ENGINEER: DRAPER ADEN ASSOCIATES
   CHRISTOPHER M. SHUST, P.E.
   8090 VILLA PARK DRIVE
   RICHMOND, VIRGINIA 23228
   (804) 264-2228, FAX (804) 264-8773

3. TAX MAP NUMBER: 24-A-11A, 24-A-12A DB. 308, PG. 79

4. SITE TABULATION:

   **A- PARKING:**

| | | |
|---|---|---|
| PROPOSED: | REGULAR | 151 SPACES |
| | ADA ACCESSIBLE | 6 SPACES |
| | TOTAL | 157 SPACES |

   **B- INTERIOR GREEN SPACE:**
   REQUIRED: (5% OF PARKING SPACE)
   =(0.05)(162 SF/SPACE)(157 SPACES)=1,272 SF
   PROVIDED: 5,564 SF

   **C- OPEN SPACE:**
   REQUIRED: (15% OF SITE AREA)
   =(0.15)(5.95 AC)(43,560 SF/AC) = 38,877 SF
   PROVIDED: 171,000± SF

   **D- GROSS SITE AREA (GSA): (W/IN LOC)** = 259,182 SF
   REDUCTIONS: BUILDING = 24,995 SF
   PARKING SPACES = 25,434 SF
   ADJUSTED GROSS SITE AREA (AGSA) = 208,753 SF
   TREE CANOPY REQUIREMENT (15% OF AGSA) = 31,313 SF
   TREE CANOPY PROVIDED (TCP) = **AC.
   PROJECTED 10 YEAR GROWTH FOR
   TREE COVERAGE (1.25 X TCP) = **AC.
   **REFER TO LANDSCAPE AND LIGHTING PLAN FOR TCP CALCS.

5. ZONING: GOVERNMENT
6. TOTAL DISTURBED AREA: 5.95 Ac.
7. PROPOSED USE: ADMINISTRATION BUILDING
8. WATER: PROVIDED BY COUNTY
9. SEWER: PROVIDED BY COUNTY
10. DIMENSIONS AND RADII ARE TO FACE OF CURB, WHERE APPLICABLE UNLESS OTHERWISE INDICATED.
11. THE CONTRACTOR SHALL SECURE ALL NECESSARY PERMITS FOR THIS PROJECT FROM PRINCE GEORGE COUNTY.
12. ANY PERMITS WHICH MUST BE OBTAINED SHALL BE THE CONTRACTOR'S RESPONSIBILITY AND AT HIS EXPENSE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ABIDING BY ALL CONDITIONS AND REQUIREMENTS OF THE PERMITS.
13. ALL DRAINAGE STRUCTURES SHALL BE BUILT AND INSTALLED IN ACCORDANCE WITH VIRGINIA DEPARTMENT OF TRANSPORTATION SPECIFICATIONS.
14. THE LOCATION OF EXISTING SEWER, WATER OR GAS LINES, CONDUITS OR OTHER STRUCTURES ACROSS, UNDERNEATH, OR OTHERWISE ALONG THE LINE OF PROPOSED WORK ARE NOT NECESSARILY SHOWN ON THE PLANS, AND IF SHOWN ARE ONLY APPROXIMATE. CONTRACTOR SHALL VERIFY LOCATION AND ELEVATION OF ALL UNDERGROUND UTILITIES SHOWN ON THE PLANS IN AREAS OF CONSTRUCTION PRIOR TO STARTING WORK. CONTACT ENGINEER IMMEDIATELY IF LOCATION OR ELEVATION IS DIFFERENT FROM THAT SHOWN ON THE PLANS, IF THERE APPEARS TO BE A CONFLICT, OR UPON DISCOVERY OF ANY UTILITY NOT SHOWN ON THE PLANS. FOR ASSISTANCE IN LOCATING EXISTING UTILITIES CALL "MISS UTILITY", 1-800-552-7001.
15. ALL WATER AND SEWER CONSTRUCTION AND MATERIALS SHALL CONFORM WITH THE LATEST STANDARDS AND SPECIFICATIONS OF PRINCE GEORGE COUNTY (REFERENCE COUNTY OF PRINCE GEORGE, DEPARTMENT OF PUBLIC UTILITIES STANDARDS FOR DETAILS.)
16. WHERE PAVEMENT IS BEING REMOVED, THE CONTRACTOR SHALL REMOVE AGGREGATE BASE MATERIAL TO SUB-GRADE.
17. DAMAGE TO UTILITIES (INCLUDING UNDERGROUND) OR PROPERTY OF OTHERS BY CONTRACTOR DURING CONSTRUCTION SHALL BE REPAIRED TO PRECONSTRUCTION CONDITIONS BY CONTRACTOR AT NO COST TO OWNER.
18. EXISTING PAVEMENT AND OTHER SURFACES DISTURBED BY CONTRACTOR (WHICH ARE NOT TO BE REMOVED) SHALL BE REPAIRED TO LIKE-NEW CONDITION AT NO ADDITIONAL COST TO OWNER.
19. THE CONTRACTOR IS REQUIRED TO MAINTAIN ALL DITCHES, PIPES, AND OTHER DRAINAGE STRUCTURES FREE FROM OBSTRUCTION UNTIL WORK IS ACCEPTED BY THE OWNER. THE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGES CAUSED BY FAILURE TO MAINTAIN DRAINAGE STRUCTURE IN OPERABLE CONDITION.
20. THE OWNER SHALL HAVE A SET OF APPROVED PLANS AVAILABLE AT THE SITE AT ALL TIMES WHEN WORK IS BEING PERFORMED. A DESIGNATED RESPONSIBLE EMPLOYEE SHALL BE AVAILABLE FOR CONTACT BY COUNTY INSPECTORS.
21. PARKING SPACES SHALL BE DELINEATED BY FOUR INCH WIDE WHITE TRAFFIC PAINT.
22. LANDSCAPING AND SITE IMPROVEMENTS WILL BE INSTALLED AND MAINTAINED SO AS NOT TO INTERFERE WITH SIGHT DISTANCE NEEDS OF DRIVERS WITHIN THE PARKING AREA AND AT ENTRANCE/EXIT LOCATIONS.
23. THE CONTRACTOR SHALL NOTIFY THE COUNTY ENGINEER AT LEAST 24 HOURS PRIOR TO STARTING WORK ON THIS PROJECT.
24. EXISTING PAVEMENT TO REMAIN SHALL BE SEALED USING SLURRY SEAL #4 AND NEW STRIPING INSTALLED.

## EROSION AND SEDIMENT CONTROL NOTES

1. ES-1. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND VIRGINIA VR 625-02-00 EROSION AND SEDIMENT CONTROL REGULATIONS.

2. ES-2. THE EROSION AND SEDIMENT CONTROL INSPECTOR IN THE PRINCE GEORGE COUNTY PLANNING DEPARTMENT MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.

3. ES-3. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING, GRADING OR LAND-DISTURBING AND SEQUENCE OF CONSTRUCTION APPROVED.

4. ES-4. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.

5. ES-5. PRIOR TO LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS OR OFF-SITE FILL ACTIVITIES, THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION CONTROL PLAN TO THE OWNER FOR REVIEW AND APPROVAL BY THE DEPARTMENT OF CONSERVATION AND RECREATION/DIVISION OF SOIL AND WATER CONSERVATION.

6. ES-6. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE DIVISION OF SOIL AND WATER CONSERVATION OF THE DEPARTMENT OF CONSERVATION AND RECREATION.

7. ES-7. SITE GRADING IS TO DRAIN TO THE PERIMETER CONTROLS AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING CONSTRUCTION, UNTIL FINAL STABILIZATION IS ACHIEVED.

8. ES-8. DURING DEWATERING, THE EFFLUENT WILL BE FILTERED OR PUMPED INTO SEDIMENT BASINS OR SILT TRAPS.

9. ES-9. THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES PERIODICALLY (AT LEAST DAILY) AND AFTER EACH RUNOFF-PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY. THE CONTRACTOR WILL MAINTAIN A LOG OF INSPECTIONS, MAINTENANCE PERFORMED AND REPAIRS MADE FOR INSPECTION BY THE OWNER AND THE DEPARTMENT OF CONSERVATION AND RECREATION/DIVISION OF SOIL AND WATER CONSERVATION.

10. MS-1. [4(1)] PERMANENT OR TEMPORARY SOIL STABILIZATION SHALL BE APPLIED TO DENUDED AREAS WITHIN SEVEN DAYS AFTER FINAL GRADE IS REACHED ON ANY PORTION OF THE SITE. TEMPORARY SOIL STABILIZATION SHALL BE APPLIED WITHIN SEVEN DAYS TO DENUDED AREAS THAT MAY NOT BE AT FINAL GRADE BUT WILL REMAIN DORMANT (UNDISTURBED) FOR LONGER THAN 30 DAYS. PERMANENT STABILIZATION SHALL BE APPLIED TO AREAS THAT ARE TO BE LEFT DORMANT FOR MORE THAN ONE YEAR.

11. MS-2. [4(2)] DURING CONSTRUCTION OF THE PROJECT, SOIL STOCKPILES SHALL BE STABILIZED OR PROTECTED WITH SEDIMENT TRAPPING MEASURES. THE CONTRACTOR IS RESPONSIBLE FOR THE TEMPORARY PROTECTION AND PERMANENT STABILIZATION OF ALL SOIL STOCKPILES ON SITE AS WELL AS SOIL INTENTIONALLY TRANSPORTED FROM THE PROJECT SITE.

12. MS-3. [4(3)] A PERMANENT VEGETATIVE COVER SHALL BE ESTABLISHED ON DENUDED AREAS NOT OTHERWISE PERMANENTLY STABILIZED. PERMANENT VEGETATION SHALL NOT BE CONSIDERED ESTABLISHED UNTIL A GROUND COVER IS ACHIEVED THAT, IN THE OPINION OF THE DIVISION OF SOIL AND WATER CONSERVATION OF THE DEPARTMENT OF CONSERVATION AND RECREATION, IS UNIFORM, MATURE ENOUGH TO SURVIVE AND WILL INHIBIT EROSION.

13. MS-4. [4(4)] SEDIMENT BASINS AND TRAPS, PERIMETER DIKES, SEDIMENT BARRIERS, AND OTHER MEASURES INTENDED TO TRAP SEDIMENT SHALL BE CONSTRUCTED AS A FIRST STEP IN ANY LAND DISTURBING ACTIVITY, AND SHALL BE MADE FUNCTIONAL BEFORE UPSLOPE LAND DISTURBANCE TAKES PLACE.

14. MS-5. [4(5)] STABILIZATION MEASURES SHALL BE APPLIED TO EARTHEN STRUCTURES SUCH AS DAMS, DIKES AND DIVERSIONS IMMEDIATELY AFTER INSTALLATION.

15. MS-10. [4(10)] ALL STORM SEWER INLETS THAT ARE MADE OPERABLE DURING CONSTRUCTION SHALL BE PROTECTED SO THAT SEDIMENT-LADEN WATER CANNOT ENTER THE CONVEYANCE SYSTEM WITHOUT FIRST BEING FILTERED OR OTHERWISE TREATED TO REMOVE SEDIMENT.

16. MS-17. [4(17)] WHERE CONSTRUCTION VEHICLE ACCESS ROUTES INTERSECT PAVED PUBLIC ROADS, PROVISIONS SHALL BE MADE TO MINIMIZE THE TRANSPORT OF SEDIMENT BY VEHICULAR TRACKING ONTO THE PAVED SURFACE. WHERE SEDIMENT IS TRANSPORTED ONTO A PUBLIC ROAD SURFACE, THE ROAD SHALL BE CLEANED THOROUGHLY AT THE END OF EACH DAY. SEDIMENT SHALL BE REMOVED FROM THE ROADS BY SHOVELING OR SWEEPING AND TRANSPORTED TO A SEDIMENT CONTROL DISPOSAL AREA. STREET WASHING SHALL BE ALLOWED ONLY AFTER SEDIMENT IS REMOVED IN THIS MANNER. THIS PROVISION SHALL APPLY TO INDIVIDUAL SUBDIVISION LOTS AS WELL AS TO LARGER LAND-DISTURBING ACTIVITIES.

17. MS-18. [4(18)] ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION, OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED UNLESS OTHERWISE AUTHORIZED BY THE LOCAL PROGRAM ADMINISTRATOR. TRAPPED SEDIMENT AND THE DISTURBED SOIL AREAS RESULTING FROM THE DISPOSITION OF TEMPORARY MEASURES SHALL BE PERMANENTLY STABILIZED TO PREVENT FURTHER EROSION AND SEDIMENTATION.

## EROSION CONTROL NOTES

1. THE CONTRACTOR SHALL INSTALL ALL EROSION AND SEDIMENT CONTROL DEVICES AS REQUIRED DURING CONSTRUCTION IN ACCORDANCE WITH THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK. ALL DEVICES REFERRED TO IN THESE PLANS CAN BE FOUND IN THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK.
2. ALL DISTURBED AREA'S SHALL BE PERMANENTLY SEEDED AND MULCHED WITHIN 7 DAYS OF REACHING FINAL GRADE. AREAS WHICH HAVE BEEN DISTURBED AND HAVE NOT REACHED FINAL GRADE, BUT WHICH ARE TO REMAIN UNDISTURBED FOR LONGER THAN 60 DAYS ARE TO BE TEMPORARILY SEEDED AND MULCHED WITHIN 7 DAYS. AS UPSTREAM AREAS ARE STABILIZED, DOWNSTREAM TEMPORARY DEVICES ARE TO BE REMOVED.
3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO PERIODICALLY INSPECT ALL SEDIMENT AND EROSION CONTROL DEVICES AND INSURE THAT THEY ARE IN GOOD WORKING ORDER. AT A MINIMUM, ALL DEVICES SHALL BE INSPECTED WEEKLY AND AFTER MAJOR RAINFALL EVENTS. ANY DEVICE NEEDING REPAIRS SHALL BE REPAIRED WITHIN 24 HOURS.
4. THE CONTRACTOR SHALL INSTALL ADDITIONAL EROSION AND SEDIMENT CONTROL DEVICES IF DURING THE COURSE OF CONSTRUCTION THE COUNTY DETERMINES THAT THEY ARE REQUIRED.
5. SILT SHALL BE REMOVED FROM SILT FENCES WHEN THE SILT REACHES APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER.
6. THE CONTRACTOR SHALL PERIODICALLY TOP DRESS THE CONSTRUCTION ENTRANCE WITH CLEAN STONE. IF THE CONSTRUCTION ENTRANCE FAILS TO REMOVE DIRT FROM THE TIRES OF VEHICLES ENTERING A PUBLIC RIGHT-OF-WAY A WASH RACK SHALL BE INSTALLED AND THE TIRES WASHED. THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ANY REQUIRED WATER FOR THE WASHING OF TIRES. DIRT TRACKED ONTO THE PUBLIC RIGHT-OF-WAYS SHALL BE REMOVED IMMEDIATELY BY THE CONTRACTOR.
7. ALL EROSION AND SILTATION MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN GRADING.
8. ALL STORM AND SANITARY SEWER LINES NOT IN STREETS ARE TO BE MULCHED AND SEEDED WITHIN SEVEN DAYS AFTER BACKFILL. NO MORE THAN FIVE HUNDRED FEET ARE TO BE OPEN AT ONE TIME.
9. ALL TEMPORARY EARTH BERMS, DIVERSIONS, AND SILT DAMS ARE TO BE MULCHED AND SEEDED FOR VEGETATIVE COVER IMMEDIATELY AFTER GRADING. STRAW OR HAY MULCH IS REQUIRED. THE SAME APPLIES TO STOCKPILES ON SITE AS WELL AS SOIL (INTENTIONALLY) TRANSPORTED FROM THE PROJECT SITE.
10. ELECTRIC POWER, TELEPHONE, AND GAS SUPPLY TRENCHES ARE TO BE COMPACTED, SEEDED AND MULCHED WITHIN FIFTEEN DAYS AFTER BACKFILL.
11. DURING CONSTRUCTION, ALL STORM SEWER INLETS WILL BE PROTECTED BY SILT TRAPS, MAINTAINED AND MODIFIED AS REQUIRED BY CONSTRUCTION PROGRESS.
12. ANY DISTURBED AREA NOT PAVED, SODDED, OR BUILT UPON BY NOVEMBER FIRST, IS TO BE SEEDED ON THAT DATE WITH OATS, ABRUZZI, RYE, OR EQUIVALENT AND MULCHED WITH HAY OR STRAW MULCH. MODIFY AS APPLICABLE DEPENDING ON PROPOSED TIME OF CONSTRUCTION.
13. THE CONTRACTOR IS RESPONSIBLE FOR APPOINTING A DESIGNATED "RESPONSIBLE LAND DISTURBER" (RLD) WHO SHALL BE RESPONSIBLE FOR INSPECTING AND MAINTAINING ALL EROSION CONTROL MEASURES. THE RLD SHALL BE CERTIFIED IN VIRGINIA.

## EROSION CONTROL QUANTITIES

| | |
|---|---|
| 1,122 LF | SILT FENCE |
| 458 LF | DIVERSION DIKE |
| 1 EA | TEMPORARY SEDIMENT TRAP |
| 13 EA | INLET PROTECTION |
| 1,050 LF | TREE PROTECTION |
| 2 EA | CULVERT INLET PROTECTION |
| 1 EA | CONSTRUCTION ENTRANCE |
| 2 EA | OUTLET PROTECTION |

## LEGEND:

**EXISTING FEATURES:**

DROP INLET & STORM SEWER
STORM SEWER & MANHOLE
SANITARY SEWER & MANHOLE
CLEANOUT
WATERLINE
WATER VALVE
WATER METER
CHECK VALVE
FIRE HYDRANT
WELL (POTABLE)
GAS VALVE
GAS DRIP
POWER POLE
LIGHT POLE / STREET LAMP
POWER/TELEPHONE LINE
CONTOUR LINE
UNDERGROUND TELEPHONE
UNDERGROUND POWER
EDGE OF PAVEMENT
CHW/HW LINES

**PROPOSED FEATURES:**

STORM SEWER & DROP INLET
STORM SEWER & MANHOLE
SANITARY SEWER & MANHOLE
CG-2
CG-6
CG-6R
CLEAN OUT
WATERLINE
LIGHT POLE / STREET LAMP
FIRE ACCESS LANE
HEAVY DUTY ASPHALT
LIGHT DUTY ASPHALT
CONCRETE SIDEWALK / APRON
COVERED SIDEWALK
UNDERGROUND POWER
CHW/HW LINES
DRAINAGE DIVIDES
PHASE LINE
FLOW PATH

**DEMOLITION**

REMOVE EXISTING CONCRETE/ASPHALT
REMOVE/ABANDON UNDERGROUND UTILITY
REMOVE TREE
REMOVE/RELOCATE FENCE, PER OWNER
REMOVE/RELOCATE SIGN, LIGHTPOST, PER OWNER

**EROSION CONTROL FEATURES**

INLET PROTECTION IP
CULVERT INLET PROTECTION CIP
CONSTRUCTION ENTRANCE CE
SILT FENCE SF
SEDIMENT TRAP ST
DIVERSION DIKE DD
TREE PROTECTION TP
LIMITS OF CLEARING & GRADING
OUTLET PROTECTION OP
DUST CONTROL DC

## EROSION CONTROL NARRATIVE

1. INSTALL CONSTRUCTION ENTRANCE AS SHOWN ON DEMOLITION AND EROSION CONTROL PLAN, PER DETAIL SHEET C3.

2. INSTALL EROSION CONTROL DEVICES AS SHOWN PRIOR TO ANY LAND DISTURBING ACTIVITIES. THE CONTRACTOR IS RESPONSIBLE FOR REMOVING EXCESSIVE SEDIMENT FROM ALL EROSION CONTROL DEVICES.IN ORDER TO MAINTAIN WORKING ORDER, UNTIL PRINCE GEORGE COUNTY EROSION CONTROL INSPECTOR AUTHORIZES DEVICE REMOVAL. THE CONTRACTOR IS ALSO RESPONSIBLE FOR MAINTAINING DRAINAGE TO THE EROSION CONTROL DEVICES THROUGHOUT THE DURATION OF CONSTRUCTION.

3. BEGIN DEMOLITION AND TREE REMOVAL.

4. INSTALL STORM AND SANITARY SEWERS AND BEGIN GRADING ACTIVITIES. ALL CONSTRUCTED INLETS ARE TO IMMEDIATELY RECEIVE INLET PROTECTION, AND ALL CONSTRUCTED OUTFALLS ARE TO IMMEDIATELY RECEIVE OUTLET PROTECTION.

5. BEGIN PARKING LOT & BUILDING CONSTRUCTION.

6. AS GRADES REACH FINAL GRADE, APPLY PERMANENT SEEDING. FOR AREAS DISTURBED BUT NOT AT FINAL GRADE, APPLY TEMPORARY SEEDING.

7. AT THE APPROVAL OF THE COUNTY EROSION CONTROL INSPECTOR, AND AFTER ALL UPSLOPE DRAINAGE AREAS HAVE BEEN STABILIZED, REMOVE SEDIMENT TRAP #1 AND COMPLETE GRADING.

8. AT THE APPROVAL OF THE COUNTY EROSION CONTROL INSPECTOR, AND AFTER ALL UPSLOPE DRAINAGE AREAS HAVE BEEN STABILIZED, REMOVE ALL REMAINING EROSION CONTROL DEVICES AND APPLY PERMANENT SEEDING.

SITE PLAN APPROVAL
PRINCE GEORGE, VIRGINIA
PLANNING/ZONING: 2-13-03
BUILDING OFFICIAL:
SITE SERVICES:
ENGINEERING/UTILITIES: BE M Brilla 2-13-03
HEALTH DEPARTMENT:
VDOT, RESIDENCY: 2-13-03
D Williams 2.13.03

*PLANS ARE APPROVED WITH THE ADDITION OF THE 2" WATER METER VAULT WHICH IS ATTACHED.


Draper Aden Associates
Engineering • Surveying • Environmental Services

Richmond, VA
8090 Villa Park Drive
Richmond, VA 23228
804-264-2228 Fax: 804-264-8773
www.daa.com

Blacksburg, VA
Charlottesville, VA
Raleigh-Durham, NC


**DAA PROJECT NO: R00532.03L**

RECEIVED FEB 10 2003

COMMONWEALTH OF VIRGINIA
CHRISTOPHER M. SHUST
No. 034028
12/20/02
PROFESSIONAL ENGINEER


HVC•• CHENAULT
henning·vest·covey·chenault architectural corporation
richmond virginia
architecture • planning • interior design


NEW COUNTY OFFICE BUILDING
PRINCE GEORGE COUNTY
PRINCE GEORGE, VIRGINIA

| | |
|---|---|
| com. no.: | 4040 |
| drawn by: | SEK |
| checked by: | CMS |
| date: | 10/01/01 |
| revisions: | 12/06/01 |
| | 05/15/02 |
| | BID:09/09/02 |
| | 1 11/04/02 |
| | 12/20/02 |

COVER SHEET

C1