RT. 156 WATERLINE EXTENSION
BLAND DIST.
PRINCE GEORGE COUNTY, VA

INDEX

Sheet No	Description
1	Cover Sheet
2	Plan Profile 0+0 to 15+0
3	Plan Profile 15+0 to 27+83
4	Details
5	Details
6	Cross Sections

VICINITY MAP 1"=2000'

NOTES

1. Elevations based on Mean.
2. Locations of underground utilities are approximate. Contractor shall verify actual location prior to excavation.
3. Owner: County of Prince George
4. Contractor: Ridge G. A. Johnson
5. Unless specifically noted all construction shall comply with the "Design and Construction of Water and Wastewater Systems", County of Prince George, Virginia, February 1979.

WATERLINE MATERIALS

1" P.V.C. C-900 pipe, SDR-18	1,963 L.F.
1" Ductile iron pipe, Class 150 p.s.i.	36 L.F.
6" P.V.C. ASTM-D, 2241, SDR-26, Class 160 p.s.i.	718 L.F.
1" x 6" x 12" D.I. M.J. tee	2 EA.
1" x 6" x 12" D.I. M.J. branch "Y"	1 EA.
1" D.I. M.J. blind flange	1 EA.
1" x 4" M.J. reducer	1 EA.
1" x 6" M.J. reducer	1 EA.
6" 22½° bend	1 EA.
6" 45° bend	1 EA.
6" tee	1 EA.
6" G.V.	4 EA.
6" blind flange	1 EA.
Hydrant (include line from main)	2 EA.
Concrete encasement	5.5 C.Y.

APRIL 24, 1981

LEGAT, ELROD AND ASSOCIATES, INC.
CONSULTING ENGINEERS AND SURVEYORS
HOPEWELL, VIRGINIA

SHEET NUMBER	DATE	DESCRIPTION

REVISIONS