GENERAL NOTES

1. WATER LINES TO BE CONSTRUCTED ACCORDING TO DESIGN STANDARDS AND SPECIFICATIONS FOR SEWER & WATER CONSTRUCTION AND IMPROVEMENTS IN PRINCE GEORGE COUNTY.
2. WATER LINE TO BE CLASS 150 TRANSITE PIPE.
3. 3/4" K-COPPER SERVICE TO METER BOX TO BE SET INSIDE RIGHT OF WAY
4. ALL WATER LINES TO EXTEND A MINIMUM OF ONE SECTION PAST VALVE BEFORE CAPPING
5. ALL CROSSES TO BE ENCASED IN CONCRETE – MIN. THICKNESS = 1'

DESCRIPTION

500'	OF	8"	W/L	STATE	ROUTE	649
630'	OF	6"	W/L	STATE	ROUTE	649
1350'	OF	6"	W/L	TEMPLE	DRIVE	

MATERIALS LIST

8" C.A. W/L	500'
6" C.A. W/L	1980'
6" VALVE	6 EA.
VALVE BOX	6 EA.
8 x 8 x 6 TEE	2 EA.
6 x 6 x 6 TEE	3 EA.
6" BLIND CAP	4 EA.
8 x 6 REDUCER	1 EA.
FIRE HYDRANT	4 EA.
SINGLE OCCUPANCY TAPS	3 EA.
DOUBLE OCCUPANCY TAPS	13 EA.
6 x 6 x 6 CROSS	1 EA.

NOTES

WATER LINES WILL BE PLACED AT A DEPTH OF 5' FROM THE FINISHED GRADE OF THE ROADS. SEE CONSTRUCTION PLANS OF INDIVIDUAL SUBDIVISIONS FOR PROFILES.

TEMPLE ESTATES WATER PLAN		
SCALE: 1" = 100'	APPROVED BY:	DRAWN BY CET
DATE: JAN 13, 1976		REVISED
WILDWOOD FARMS WATER PROJECT		
CHARLES C. TOWNES & ASSOCIATES ENGINEERS, PLANNERS, LAND SURVEYORS COLONIAL HEIGHTS, VA.		DRAWING NUMBER 5 of 10

24X36 PRINTED ON NO. 1000H CLEARPRINT